

NFPA 13D Requirements per Town / District

| Town/District | Year Passed | Before meter/ Through Meter | Backflow Type | Garage | Closets / Bathrooms | 6" Bell | Exterior Horn Strobe | Addition Percentage | Edition of 13D Using | Other/Misc | Self Review Time | Consultant Review Time | Fees |
|---|-------------|-----------------------------|---------------|-------------------|--------------------------|-------------------------------|----------------------------------|------------------------------|----------------------|---|------------------|------------------------|----------------|
| Justice | 2005 | After | Double Check | Yes | Walk-ins per NFPA 13D | Yes/HVAC | Townhomes: Yes Single Family: No | 40% remodel | 2003 | Min.2"supply & separate meter | unknown | unknown | unknown |
| Libertyville (Municipality) | 2005 | Before | Double Check | Yes | Per 13D | Yes | Yes | No | 1999 | | 10 Days | Self | \$150 |
| Libertyville FPD | 2005 | Before | Double Check | Yes | Per 13D | Yes | Yes | No | 1999 | | 10 Days | Self | \$150 |
| Lincolnwood | 2005 | After | Double Check | Yes | Yes | Yes | Yes | 50% | 2006 | | 7 Days | FSCI | > \$200 |
| Mattewa | 2005 | Before | Double Check | Yes | Per 13D | Yes | Yes | No | 1999 | | 10 Days | Self | \$150 |
| Oak Forest | 2005 | After | Double Check | Per 13D | Per 13D | Required | Yes | 50% | 2003 | | 2 days | Self | No Charge |
| St. Charles Countryside FPD Wayne; Wasco (Hold) | 2005 | Varies | Double Check | Modified | No | Per 13D | No | 25% | 2002 | No Closets/Pantry/ Bathrooms | unknown | unknown | unknown |
| Sunnycrest FPD | 2005 | Before | Double Check | Per 13D | Yes | Yes | Yes | per county | 2006 | | n/a | consultants | unknown |
| River Forest | 2006 | After | Double Check | Per 13D | Per 13D | Yes | Yes | 50% | 2002 | | < 1 month | self | No Charge |
| Glenwood | 2006 | After | Double Check | No | Per 13D | No | Yes | 50% | 2006 | | 7 days | Self | No Charge |
| Villa Park | 2006 | Before | Double Check | Yes | Per 13D | Vent | Yes | 50% or 1,500 Sq. Ft. or More | 1999 | | < 2 weeks | Self | \$50 per riser |
| Oakbrook Terrace | 2006 | Before | Double Check | Yes | Per 13D | Yes | No | 50% | 1999 | | 10 Days | Self | \$75 |
| Prospect Heights | 2006 | | | | | | | | | Many non-water supply areas | | | |
| Northbrook | 2007 | After | Double Check | Yes | Per 13D | Yes | Yes | 40% Outside Walls | 2002 | | 5-7 days | Self | \$180-\$225 |
| Lake Bluff | 2007 | To Be | | Yes | | Yes | Yes | 75% | 2002 | | | | \$150 |
| Lake Zurich FPD | 2007 | Tank/Pump | Rural water | Yes | Per 13D | No | Yes | No | 2007 | Monitoring/Inside Strobe | 7 days | Self | \$200 |
| Lincolnshire/Riverwoods FPD | 2007 | After | RPZ | Yes | Per 13D | 10 Inches | Yes | 50% Cost/Size | 2002 | Monitoring /inside strobe each floor/knox box | 10 Days | Self | \$100 |
| Highwood | 2007 | thru | either | yes,when attached | per 13D | no | yes | Addition story | 2006 | | 2 weeks | unknown | \$200 |
| Bellwood | 2007 | Before | Double Check | 100% Coverage | Per 13D | No Bell if Burgler Alarm Tied | Yes | | | | 10 Days | | |
| Aisip | 2007 | Before | Double Check | No | Per 13D | Yes/HVAC | Required | 50% of Assessed Valuation | 2006 | Per Ill. Plumbing Code 1 1/2" | | 5 Days | Unknown |
| Palatine Rural FPD | 2007 | tank/pump | rural water | No | Per 13D | Yes/HVAC | Yes | 75% remodel | 2002 | | >2weeks | self | \$140 |
| Chicago Ridge | 2007 | before | Double check | no | per 13 D | Yes/Hvac | Yes | No | 2006 | Knox Box | 2 weeks | Self | \$100 |
| Orland Park | 2007 | Before | Double check | no | per 13D | Yes/Hvac | no | | 2002 | | <2 weeks | consultants | \$110 |
| Highwood | 2007 | Before | Double check | no | Per 13D | yes/Hvac | no | 2nd story addition | 2006 | Knox Box if Alarmed | <2 weeks | consultants | yes |
| Lisle Woodridge | 2007 | | | | | | | | | | | | |
| Pleasantview FPD | 2008 | | | | | | | | | | | | |
| Country Club Hills | 2008 | After | Dbl Ck or RPZ | Attached yes | Per 13D | Yes/Hvac | yes | over 50% | 2007 | | <2weeks | self | unknown |
| Park Forest | 2008 | | | | | | | | | | | | |
| Newport Township | 2009 | | | | | | | | | | | | |
| Green Oaks | 2009 | Before | Double Check | Yes | Per 13D | Yes | Yes | No | 1999 | | 10 Days | Self | \$150 |
| Riverside | 2009 | After | Double check | Per 13D | Per 13D | Yes | Per 13D | No | 2006 | | 1 week | consultant | 10 day fee |
| Palos Heights | 2009 | | | | | | | | | | | | |
| Lake Zurich | 2009 | After | Double Check | Yes | Per 13D | No/H/S | Yes | No | 2007 | | 1 week | N/A | Varies |
| Lake Zurich Commercial | 1997 | After | RPZ | 13 | All Baths Closets Per 13 | No/ H/S Only | Yes | Over 3000 | 2007 | | 1 week | N/A | Varies |

NFPA 13D Requirements per Town / District

| Town/District | Year Passed | Before meter/ Through Meter | Backflow Type | Garage | Closets / Bathrooms | 6" Bell | Exterior Horn Strobe | Addition Percentage | Edition of 13D Using | Other/Misc | Self Review Time | Consultant Review Time | Fees |
|---------------------------------------|-------------|-----------------------------|---------------------|---|-----------------------------|-------------------|----------------------------|--|----------------------|--|------------------|------------------------|-------------|
| <i>Long Grove (Municipality)</i> | 1988 | N/A | Double Check | Yes | Per 13D | Required | Strobe Only | Most new construction | 1999 | | 10 days | Varies | \$200 |
| <i>Barrington FPD</i> | 1997 | Before | Double Check | No | Per 13D | Required | Required | 100% Remodel | 1996 | 3/4 Tank & Pump; 1/4 off of just well pump/ff 35 GPM or more | 7 Days | N/A | No Charge |
| <i>Village of Barrington</i> | 1997 | N/A | Double Check | No | Per 13D | Required | Required | 100% Remodel | 1996 | 3/4 Tank & Pump; 1/4 off of just well pump/ff 35 GPM or more | 7 Days | N/A | No Charge |
| <i>Lake Barrington</i> | 1997 | N/A | Double Check | No | Per 13D | Required | Required | 100% Remodel | 1996 | 3/4 Tank & Pump; 1/4 off of just well pump/ff 35 GPM or more | 7 Days | N/A | No Charge |
| <i>Clarendon Hills</i> | 2000 | After | Double Check | No | Per 13D | Per 13D | Required | More than 50% of outside walls or add > 125% | 2006 | | < 2 weeks | FSCI | Unknown |
| <i>Hoffman Estates</i> | 2000 | Before | Double Check | No | Per 13D | Required | White Horn/Strobe Required | Only on total rehab | 1999 | | < 1 week | FSCI | \$380 |
| <i>Wheeling</i> | 2000 | Before | Single | Required | Walk-ins | Smoke | No | 110% | 2002 | Iron Pipe | 3 Weeks | Self | \$125 |
| <i>Park Ridge</i> | 2001 | | | No | Mechanical Electric per 13D | Required Yes HVAC | Required | Most new construction | 2002 | Omit Sprinkler in certain area | Variable | Jay singh | \$200 |
| <i>West Dundee</i> | 2001 | Before | Double Check | No | Per 13D | Required | Exterior Strobe | New construction only | 1996 | Less done in cubic Feet | Unknown | Unknown | Unknown |
| <i>Glen Ellyn</i> | 2002 | Both | Double Check | No | Per 13D | Yes/HVAC | Outside 10" Bell/Hi Sok | 150%/Class III Addition | 1999 | | < 2 Weeks | Self | No Charge |
| <i>Round Lake Beach</i> | 2002 | Before | Double Check or RPZ | Required | Per 13D | Required | No | All bathrooms NO requirements | 1999 | | 3 Days | Self | > \$75 |
| <i>Streamwood</i> | 2002 | Before | Double Check | No | Per 13D | Required | Required | No | 1999 | | < 2 Weeks | Self | No Charge |
| <i>Berkeley</i> | 2003 | Before | Double Check | Option | Per 13D | Required | exterior horn strobe | | 2006 | | N/A | FSCI | \$200 |
| <i>La Grange Park</i> | 2003 | Before | Double Check | Required | Per 13D | Required | Required | New construction only | 1999 | | | FSCI | \$242 |
| <i>Mt. Prospect</i> | 2003 | | Double Check | Required | Per 13D | Required | Bell: Yes | 150% more of living area | 2002 | | 14 Days | Self | \$180 |
| <i>Countryside FPD</i> | 2004 | Before | Double Check | Required | Per 13D | 10"bell | Required | New construction only | 1996 | | 5 Days | Self | \$200 |
| <i>Huntley FPD</i> | 2004 | Through | Double Check | Use of inside wall only for dry sidewalls | Per 13D | Yes/HVAC | "White" Horn/Strobe | No | 2002 | | 5-7 Days | B and F | \$200 |
| <i>Indian Creek (Countryside FPD)</i> | 2004 | Before | Double Check | Required | Per 13D | 10" Bell | Required | New construction only | 1996 | | 5 Days | Self | \$200 |
| <i>Long Grove FPD</i> | 2004 | N/A | Double Check | Required | Screened in porch | Required | Required | Just the addition | 1999 | | 7 Days | Self | \$200 |
| <i>Matteson</i> | 2004 | Before | Double Check | No | Per 13D | | Required | | 1999 | | | FSCI | \$50 |
| <i>North Maine FPD</i> | 2004 | Before | Double Check | Required if living sp.above | Per 13D | Required | Required | 100% increase yes, and or addn. is 50%or more of assesed value | 2002 | | 10 Days | | \$90 |
| <i>Skokie</i> | 2004 | After | Double Check | Required | Per 13D | Required | Required | No | 2003 | | < 2 Weeks | Self | No charge |
| <i>Bedford Park</i> | 2005 | | Double Check | Attached Only | Per 13D | Required | Required | 75% | 2000 | | 2-3 weeks | Self | 10% of cost |
| <i>Bridgeview</i> | 2005 | After | Double Check | No | Per 13D | Required | Outside required | 50% of original square foot or 50% of | 2000 | | | FSCI | Unknown |
| <i>Des Plaines</i> | 2009 | After | Double Check | No | Per 13D | Required | Required | No | | | > 7 days | Self | > \$75 |
| <i>Hickory Hills</i> | 2005 | After | Double Check | No | Per 13D | Required | Required | No | 1999 | Min.2"supply & separate meter | < 7 Days | Self | <\$100 |